

QUOTATION

Quotation No.: MRG/TK/73716 R1

Quotation Date: 10/07/2026

MRG TRN: 100054873300003

Main Contractor	: M/s. Al Shafar National Contracting L.L.C.
Address	: 68P4+HJ7 - Oud Metha - Dubai
Contact	: +971 4 33 66 222
Attn.	: Mr. Ahmed Salam

Project	: (P171) G+2P+6+HC Retail & Residential Building
Location	: Plot No. 591-1803, Jabal Ali 1st - 591, Dubai, UAE
Client	: M/s. Zoya Properties
Consultant	: M/s. Arkiplan Consulting Architects & Engineers

Bill of Quantity:

SL No.	Description of Works	Unit	Approx. QTY.	Rate AED	Amount AED
	THERMAL AND MOISTURE PROTECTION TO SUBSTRUCTURE				
1-	<u>One layer of 1000 gauge polythene sheets; all in accordance with the drawings and specification</u>				
A.	To Raft Slab	m2	2,259.00	-	N/A
B.	Below Grade Slab	m2	1,800.00	-	N/A
2-	<u>2 layers of 4mm thick SBS waterproofing membrane 180gm/m2 from Awazel or Equivalent</u>				
A.	Horizontally to Raft Slab	m2	2,184.00	62.00	135,408.00
B.	Vertically To Raft Slab & water tank	m2	486.00	62.00	30,132.00
3-	<u>2 coats of bituminous waterproofing, complete; all in accordance with the drawings and specification</u>				
A.	Horizontally & vertically	m2	3,010.00	17.00	51,170.00
4-	<u>3mm thick Protection board; all in accordance with the drawings and specification</u>				
A.	Vertically	m2	486.00	24.00	11,664.00
5-	Water Tank Water Proofing				
	<u>Waterproofing to water tank all in accordance with drawings and specification</u>				
A.	Ref. GRP-01, 5mm thick GRP lining	m2	145.00	-	N/A
B.	Ref. GRP-02, 4mm thick GRP lining	m2	345.00	-	N/A
C.	Ref. GRP-03, 3mm thick GRP lining	m2	145.00	-	N/A

QUOTATION

Quotation No.: MRG/TK/73716 R1

TO SUPER STRUCTURE					
6-	Waterproofing system to foundations of A/c Machines, water tanks, cleaning cradle and the like complete, as per drawings and specifications.				
A.	To Equipment Foundations (1-layer 4mm)	Item	1.00	-	N/A
Waterproofing For Wet Areas Kitchens, Toilets & Exposed Balconies					
7-	<u>Supply and apply acrylic based liquid applied waterproofing to form uniform membrane layer (approx. 0.8 to 1mm however not more than 1.5mm thick) all in accordance with drawings and specification</u>				
A.	Horizontally	m2	2,156.00	28.00	60,368.00
B.	Vertically	m	2,850.00	9.00	25,650.00
C.	OTS Shaft Waterproofing	m2	26.00	28.00	728.00
8-	Roof Water Proofing – By WEBER – Option 1				
	Ref: CRS-01, Combo Roof waterproofing system, complete, as per drawings, specifications and engineers' approval.				
A.	Dressing roofing system into rain water outlets, including waterproofing, flashings, etc., complete	m2	1,104.00	154.00	170,016.00
	Dressing roofing system into pipe penetration, including waterproofing, flashings, etc., complete				
8-	Roof Water Proofing – By Royal Industries - Option 2				
	Ref: CRS-01, Combo Roof waterproofing system, complete, as per drawings, specifications and engineers' approval.				
A.	Dressing roofing system into rain water outlets, including waterproofing, flashings, etc., complete	m2	1,104.00	148.00	Rate only
	Dressing roofing system into pipe penetration, including waterproofing, flashings, etc., complete				
ADDITIONAL ITEMS					
9-	Waterproofing to Pool deck area				
	1-layer – NO WARRANTY – Not Recommended				
A.	(2 layers Recommended) 4mm thick SBS membrane 180gm/m2 from Awazel or equivalent (horizontal) with 10-years warranty	m2	227.00	62.00	14,074.00
	1-layer – NO WARRANTY - Not Recommended				
B.	(2 layers Recommended) 4mm thick SBS membrane 180gm/m2 from Awazel or equivalent (vertical 300mm ht.) with 10-years warranty	m	69.00	19.00	1,311.00
C.	50mm thick protection screed	m2	227.00	-	N/A
10-	Waterproofing to water feature at first floor terrace				
A.	1-layer 4mm thick SBS membrane 180gm/m2 from Awazel or equivalent (horizontal)	m2	135.00	32.00	4,320.00
B.	50mm thick protection screed	m2	135.00	-	N/A

QUOTATION

Quotation No.: MRG/TK/73716 R1

C.	Acoustic insulation to walls and soffit of health club	m2	201.00	-	N/A
D.	Insulation to wall in void area at Podium-1	m2	32.00	-	N/A
11-	Waterproofing to pool pump room and terrace at first floor				
A.	1-layer 4mm thick SBS membrane 180gm/m2 from Awazel or equivalent (horizontal)	m2	1,053.00	32.00	33,696.00
B.	1-layer 4mm thick SBS membrane 180gm/m2 from Awazel or equivalent (vertical) 300mm ht	m	570.00	10.00	5,700.00
C.	50mm thick protection screed	m2	1,053.00	-	N/A
Total Amount Excl. VAT					544,237.00
5% VAT					27,211.85
Total Amount Incl. VAT					571,448.85

Payment Terms:

MEMBRANE WATERPROOFING

- 20% Advance via CDC against dated security cheque via CDC (deductible from progressive invoice).
- 100% Progressive via CDC within 15 days from the date of Proforma invoice submission.

COMBO ROOF WATERPROOFING

- 20% Advance via CDC against dated security cheque (deductible from Progressive Invoice)
- 60% After Water Test via CDC within 15 days from the date of Proforma invoice
- 30% After Screed via CDC within 15 days from the date of Proforma invoice
- 10% After completion via CDC within 15 days from the date of Proforma invoice

Exclusion:

1. The main contractor is responsible for providing free electricity and water for cleaning, flood tests etc.
2. The main contractor will supply sand and cement for sloping panels, angle fillets etc.
3. The main contractor is responsible for providing Boom Loader for shifting the materials.
4. The Main Contractor shall be responsible for all surface preparation required.
5. Water for the water test, including filling and removal, will be provided by the main contractor.
6. Access to the site for machinery and covered material storage area at site.
7. Shifting of materials to the required work area from storage to work location Boom loader, Bob CAT and JCB will provide by main contractor.
8. Surface preparation to be done by main contractor.
9. Complete access at site to execute the works shall be provided by main contractor like crane, lights, access to roof etc.
10. Any opening less than 1 (one) m² will not be deducted.
11. Skirting will be calculated based on square meters using the formula Perimeter x 0.25m.
12. **Force Majeure:** If by reason of war, hostility, lock-out, strikes, embargoes, or any act of GOD, the fulfillment of this contract shall be deemed to be null and void and no liability shall be attached to us.

Terms & Conditions:

1. The job shall commence upon receipt of the official work order and agreed advance payment.
2. Any work not explicitly included in the scope of work shall be treated as a variation and will be charged separately, with applicable cost and time implications.

QUOTATION

Quotation No.: MRG/TK/73716 R1

3. Joint measurement must be conducted and approved prior to commencement of work and/or mobilization.
4. All executed quantities are subject to re-measurement and shall be jointly verified upon completion.
5. All gate passes, access permits, road permits, and authority approvals (if required) shall be arranged by the Main Contractor for both labor and equipment.
6. In case of building height exceeding 30 meters or in the absence of pump access, suitable arrangements such as boom placer or alternative approved methods shall be provided by the Main Contractor at their cost.
7. The quantity will be re-measurable.
8. Payment shall be made strictly as per certified invoices/payment certificates. All payments must be released within 7 days from the invoice date. In case of delay or partial payment, MRG reserves the right to suspend works until full payment is received.
9. In case of delayed payment, MRG reserves the right to impose a delay penalty of 1% per day, capped at a maximum of 10% of the total contract value.
10. Ownership of all materials supplied by MRG shall remain with MRG until full payment is received.
11. MRG reserves the right to suspend or terminate the agreement in case of breach of contractual terms by the Main Contractor.
12. Upon termination, the Main Contractor shall settle all outstanding dues including executed work, supplied materials, and demobilization costs.
13. All variations shall have corresponding cost and time implications and must be approved prior to execution.
14. Both parties shall maintain strict confidentiality of all technical, commercial, and contractual information.
15. Any disputes shall be governed and resolved in accordance with the applicable laws of the United Arab Emirates and the Emirate of Dubai.
16. All legal and recovery costs arising from delayed or non-payment shall be borne by the Main Contractor.
17. **Force Majeure:** MRG shall not be liable for any delay or failure to perform its obligations due to events beyond its reasonable control, including but not limited to acts of war (declared or undeclared), regional conflicts, civil unrest, government restrictions, sanctions, blockades, or disruption of supply chains and logistics networks. In such cases, the project timeline shall be extended accordingly without penalty.
18. **Material Price Fluctuation:** In the event of significant fluctuation in material prices (including but not limited to cement, bitumen, chemicals, fuel, or imported materials) due to market conditions or global events, MRG reserves the right to revise the quoted rates with prior notice.
19. **Supply Chain & Logistics Delays:** MRG shall not be held responsible for delays arising from material unavailability, shipping delays, port congestion, customs clearance issues, or international logistics disruptions. Such events shall entitle MRG to a reasonable extension of time without penalties.
20. **Program Dependency:** MRG's work schedule is dependent on-site readiness, access, and completion of preceding works by others. Any delays caused by the Main Contractor or other parties shall result in entitlement to extension of time and associated costs.
21. **Storage & Material Protection:** The Main Contractor shall provide secure and suitable storage space at site. MRG shall not be responsible for damage, theft, or deterioration of materials due to improper storage or site conditions.
22. **Warranty Conditions:**
 - Warranty shall be valid only upon full and timely payment.
 - Any third-party interference, modification, or damage without written approval from MRG will void the warranty.
 - Proper maintenance as per MRG guidelines is required.
 - MRG must be officially informed of any modification affecting the waterproofing system after project handover. Failure to do so will result in cancellation of warranty.
23. All rates are exclusive of VAT. A 5% VAT shall be applied as per the regulations of the UAE Federal Tax Authority.
24. In case of increasing of market prices in future then MRG reserve the rights to increase their prices.

QUOTATION

Quotation No.: MRG/TK/73716 R1

Validity:

1. Quotation is valid for 05 days only.

We hope our offer meets with your requirement and looking forward to hear from you.

Thanking you and we assure you our best service throughout.

For MRG Insulation Works LLC